

□ LARGE COMMERCIAL PROJECTS □

839 COLLINS STREET (Y3)

Situation

39,000sqm of office space over 20 floors. Simple and easy installation. First building in Melbourne that achieves workspace occupancy ratio of 1 person per 8sqm.

Task

Provide a modular lighting system that will be used as general lighting throughout the building. Underfloor power solution. Provide with detailed drawings to assist with installation.

Action

2480 floor boxes pre-wired WBC 5PIN loom solution. 5core cable for feeds from the switchboard. Locally manufactured product that is pre-tested before being sent to site.

Result

Providing nearly 25,000m of 5 core cable for feeds from the switchboard to the field. Each aspect of the install being marked up in conjunction with the project manager. Product made locally reducing lead times for 12 weeks to 3-4 weeks. More than 7,600 DALI Light Fittings.



Client
Prime Electrical

Project Scope
Turnkey soft wiring solution for light and power

Location
Melbourne VIC

Products Used
100+ boards, 7,000+ Lights and 6,000+ Power points

Tags
Health, Light, Power, WBC, MLEX

“The MyModular system works really well with the install methods that we’re used to and incorporates the specified lighting systems easily. The soft wiring between floor boxes makes install really simple and saves us time.”

Geoff Tabone Project Manager – Prime Electrical and Data